

(Witherington, 1992). If beach nourishment occurs during the sea turtle nesting season, lighting associated with construction activities on the beach may effect hatchlings and nesting females. Research has shown that low-pressure sodium (LPS) lights that emit only yellow wavelengths do not attract hatchlings (Dickerson and Nelson 1989; Nelson and Dickerson, 1989b). Witherington (1992) demonstrated that LPS lights on the beach did not significantly effect the nesting behavior of green or loggerhead sea turtles. The use of LPS lighting at the beach nourishment site and on the dredge can reduce the potential for lighting effects on sea turtles. However, the Corps is currently evaluating the appropriateness of using LPS lights in a marine construction environment for safety reasons. If, in consultation with the USFWS and FDEP, it is found not to be appropriate to use in this situation, LPS lights would not be required.

4.3.2 PROPOSED BORROW AREA: EBB SHOAL AT BAKERS HAULOVER INLET

The material within the proposed borrow areas that will be dredged and placed on the beach is similar to the existing beach sand, is low in silt content and therefore, would be compatible with sea turtle nesting. As previously mentioned in Section 2.1.1, the water depth within the proposed borrow area is too shallow for a hopper dredge. Therefore, none of the potential impacts to sea turtles that can be associated with hopper dredging would occur. It is anticipated that a hydraulic pipeline dredge would be used to perform the work. No impacts are expected on sea turtles from using this type of dredge (NMFS Regional Biological Opinions dated August 25, 1995, amended September 25, 1997).

4.3.3 BORROW AREA SOUTH OF GOVERNMENT CUT

Hopper dredging in harbors and entrance channels is known to adversely effect sea turtles by entrainment. These incidents occur because sea turtles utilize and are concentrated in these channels during certain times of the year. Sea turtles utilize hardground and reef areas for foraging and resting and may be present on the hardground areas adjacent to the proposed borrow areas during dredging. It is not expected that sea turtles will concentrate in the sandy borrow area as they do in navigation channels; therefore it is unlikely that the dredge draghead will come into direct contact with a sea turtle. Since the boundary of the borrow area is designed to avoid hardgrounds, it is not expected that the hopper dredge will have a direct impact on any sea turtles utilizing the hardgrounds for resting or foraging. To further ensure that sea turtles are not entrained by the dredge, the use of a draghead designed to deflect sea turtles would be required on the dredge. The deflector draghead is designed to form a sand wedge in front of it that will push out of the way any sea turtle that it comes in contact with. The deflector draghead has been successfully used in the maintenance dredging of navigation channels along the Southeastern United States. During past beach

nourishment projects there has been no evidence of sea turtles being entrained by a hopper dredge dredging sand material from an offshore borrow area. The material within this borrow area is similar to the existing beach sand, is low in silt content and therefore, would be compatible with sea turtle nesting.

4.3.4 UPLAND SAND SOURCE

The material obtained from an upland source would be predominantly quartz which would replace a predominantly calcium carbonate beach. It is not expected that the quartz sand itself would significantly effect nesting sea turtles or hatching success since the majority of the high density nesting beaches in Florida are comprised of predominantly quartz sand (i.e., Brevard County). However, some of the other negative impacts previously discussed (sand compaction, potential for scarp formation, artificial lighting effects, etc.) would still apply.

4.3.5 NO ACTION ALTERNATIVE (STATUS QUO)

If no action is taken, the beach would continue to erode. If left to erode, this could ultimately result in the loss of sea turtle nesting habitat and/or poor nest site selection. No adverse impacts are expected on other listed species.

4.4 FISH AND WILDLIFE RESOURCES

4.4.1 BEACH RENOURISHMENT ACTIVITIES

During the placement of sand on the beach there may be some interruption of foraging and resting activities for shorebirds that utilize the project area. This impact would be short-term and limited to the immediate area of disposal and time of construction. There would be sufficient beach area north and south of the renourishment sites that can be used by displaced birds while construction takes place. Increased foraging opportunities for some species, such as sea gulls, can also occur as a result of the discharge activity. Elevated turbidity levels within the immediate vicinity of the discharge site may interfere with foraging by sight feeders such as the brown pelican (*Pelecanus occidentalis*). However, increased turbidity levels would be limited to a small portion of the shoreline and should not result in significant impacts to foraging activities.

The disposal of sand on the beach would have temporary impacts to the macroinfaunal community. Some organisms may be buried and lost, but many organisms inhabiting the intertidal zone are well adapted for burrowing and would be able to burrow up through the fill material and survive. Turbidity levels along the disposal site would temporarily increase, but would return to normal after beach equilibrium is achieved. Organisms inhabiting this zone would be impacted by the run off from the disposal area but are adapted for survival in such conditions and impacts should be minor. Dominant infaunal inhabitants of the intertidal zone, such as amphipods, isopods and polychaetes typically possess high fecundity and rapid turnover rates

during their breeding season. Because of this, any losses due to construction activities would be replaced within a short time. No long-term adverse effects are anticipated to the intertidal macroinfaunal community due to nourishment activities (Deis, et al. 1992, Nelson 1985, Gorzelany & Nelson 1987, USFWS 1997).

Minimal impacts to nearshore hardbottom communities are expected by sand placement (i.e., disposal) on the beach due to the distance of the reefs to the shore. In conjunction with the Coast of Florida Erosion and Storm Effects Study, the hardbottom areas offshore of Dade County were mapped using side scan sonar. In addition, aerial photography flown in July 1997 has also been used to map the nearshore hardbottom. The closest hardbottom community in the vicinity of the proposed beach fill at Haulover Beach Park is in excess of 800 feet offshore (figure 5).

4.4.2 PROPOSED BORROW AREA: EBB SHOAL AT BAKERS HAULOVER INLET

Organisms similar to the beach macroinfaunal community can be found in the proposed borrow area. Dredging would result in the loss of these organisms; however, recolonization is expected to be fairly rapid. In a study of a borrow area located offshore of Delray Beach, Florida, Bowen and Marsh (1988) concluded that recovery of the infaunal community occurred within 1 year. Cutler and Mahadevan (1982) found no significant differences in biotic communities between borrow sites and surrounding areas off Panama City, Florida, some 3-4 years after a beach nourishment project. No long-term adverse impacts are expected to macroinfaunal communities that inhabit the proposed borrow site.

There are no hardbottom communities present within the proposed borrow area. The western edge of the first reef (hardbottom habitat) comes within approximately 400 feet of the eastern tip of the borrow area. Proper controls and procedures would be utilized to avoid the mechanical damage, which could result from the dredge or associated equipment coming in contact with the hardbottom. The reef edge would be marked with buoys to prevent encroachment by the dredge, and no anchoring would be permitted in hardbottom areas. The discharge pipeline would be placed in sand areas only, between the borrow area and the beach. Recording and displaying, real-time precision electronic location equipment would be in use during dredging operations. This equipment would provide the precision equivalent to that of a differential GPS system, provide records of the exact position of the dredge to the operator and allow continuous monitoring of the dredge location during operations.

To further protect the reefs in the vicinity of the borrow area a reef monitoring program would be conducted. The program would monitor and evaluate numerous biological and physical characteristics and

indicators for signs of stress or impact related to construction activities. This comprehensive program is designed to identify factors that may contribute to or cause stress and minor impacts, before they cause non-reversible impacts. Among the parameters assessed in the monitoring program are: benthic community structure, including hard coral, sponge and algal populations; fish populations of the hardbottom areas; infaunal assemblages of the beach area and borrow area; water quality, including nutrients, light penetration, turbidity and physical characteristics. These factors will be surveyed prior to and after project construction, and will be monitored regularly during project construction. The monitoring plan is described in Appendix E, *Physical and Biological Monitoring Program for Miami-Dade County, Florida, Beach Erosion Control and Hurricane Protection: Bal Harbour/Haulover Beach Renourishment*.

4.4.3 BORROW AREA SOUTH OF GOVERNMENT CUT

Dredging impacts to the macroinfaunal communities within the SGC-EXT-2 borrow area would be similar to that discussed for the proposed ebb shoal borrow area.

The borrow area is located between the second and third reef hardbottom communities. Sessile organisms associated with the hardbottom community may be susceptible to some degree of negative impact due to dredging. Potential adverse impacts to these communities may occur due to suspended sediments settling onto the reef, mechanical damage from contact by the dredge drag arm with the reef, or turbidity. As a group, scleractinian corals are the most sensitive to potential impacts. Gorgonian corals, sponges, and some other sessile organisms are more tolerant of increased turbidity and sedimentation. Past occurrences of mechanical and/or sedimentation damage to reef communities have been documented for the renourishments at Sunny Isles in 1988 and at Bal Harbour in 1990. Mechanical damages in 1988 and 1990 to reefs were from contact with the dredge drag-arm. In the 1988 incident, the dredge damaged hardbottom outside the designated dredging area. In the 1990 incident the dredge caused damage to previously undiscovered hardbottom within the designated dredging area. Sediment impacts to the reef during the 1990 incident was caused by the dredge spending a significant amount of time dredging a in one confined area between reefs located immediately north and south of the area dredged. Blair and Flynn (1988) and Blair et al. (1990) discuss factors believed to have contributed to the impacts documented, and recommended modifications to project specifications to reduce or eliminate the impacts. If any of these borrow areas were to be used for this project special considerations would be incorporated to avoid or minimize the potential for impacts to the hardbottom communities.

A buffer zone with a minimum distance of 400 ft from any hardbottom area would be established. Extensive turbidity monitoring would be performed at the dredging sites, throughout the construction phase of the project to ensure levels of turbidity are maintained below the State water quality standard. Visual inspections of the hardbottoms adjacent to the borrow area would be performed. The regions of hardbottom in proximity to the dredging area would be surveyed routinely to look for any indicators of turbidity or sediment impacts. Marine biologists with experience in impact assessment would conduct the surveys and examine the benthic organisms for pre-defined indicators of stress or imminent impact. Findings of such indicators would cause actions ranging from consultation to halting of the dredge operations until a determination can be made as to the cause and rectification of the factors creating the stress or imminent impact. The established buffer zones, borrow area usage restrictions and visual inspections of the reef would minimize or eliminate turbidity and sedimentation impacts.

Proper controls and procedures would be utilized to avoid the mechanical damage, which could result from the dredge or associated equipment coming in contact with the hardbottom. Project and construction specifications that would prevent such damage are: (a) Recording and displaying, real-time precision electronic location equipment must be in use during dredging operations. This equipment would provide the precision equivalent to that of a differential GPS system, provide records of the exact position of the dredge to the operator and allow continuous monitoring of the dredge location during operations. Daily reports would include a plot indicating the dredge location while operating in or within a quarter of a mile of the borrow area, keyed to a printout listing coordinates at specified time intervals. (b) Pipelines would be placed only in approved locations and anchoring would be permitted in sandy areas only. (c) The borrow area perimeter will be marked by placement of Coast Guard approved lighted buoys. The buoys will be placed at an interval no greater than 400 ft apart, at every change of direction of the borrow area, and no closer than 400 feet from any hardbottom area. The distance of all borrow area buoys from the hardbottoms will be verified by divers and their positions recorded. (d) The edge of the hardbottoms adjacent to the borrow area will be marked by buoys at a sufficient frequency to visually discern the line of hardbottom edge. All buoys (borrow area and hardbottom) will be checked regularly, and replaced or repositioned as necessary, throughout the period of construction. (e) The Corps and Dade County DERM have developed a procedure that would allow suspension or alteration of the dredging operation if monitoring by DERM indicates a problem.

Additional measures to protect the reefs in the vicinity of the borrow area would include an intensive reef monitoring program. The program would monitor and

evaluate numerous biological and physical characteristics and indicators for signs of stress or impact related to construction activities. This comprehensive program is designed to identify factors that may contribute to or cause stress and minor impacts, before they cause non-reversible impacts. Among the parameters assessed in the monitoring program are: benthic community structure, including hard coral, sponge and algal populations; fish populations of the hardbottom areas; infaunal assemblages of the beach area and borrow area; water quality, including nutrients, light penetration, turbidity and physical characteristics. These factors will be surveyed prior to and after project construction, and will be monitored regularly during project construction.

Rock, shell and coral rubble material that would be dredged up with the sand, but unsuitable for placement on the beach (i.e., >1 in. diam.), would be placed in a permitted artificial reef site. The habitat in the area where the rock is deposited, would change from what is now a predominantly sand benthic macroinfaunal community to a hardbottom benthic community. The rock would provide a concentrated hard substrate suitable for colonization by sessile benthic organisms. This would allow for the development of coral, plant, invertebrate and vertebrate communities and would provide a viable habitat with refuge, food resources, and a potential breeding ground for a wide variety of marine organisms. This would be the best use of this material, as the rock separated from the sand would be, and have been, devoid of external epibiotic growth (algae, sponges, coral, encrusting organisms) at the time of removal. The rock material that would be disposed in the artificial reef site is clean natural material.

To use the SGC-EXT-2 borrow area would most likely require using a hopper dredge. Because of the water depth required for a hopper dredge, it must remain seaward of the first reef tract to pump material to the beach. It therefore, would be necessary to place a discharge pipeline across the reef from an offshore pump-out platform to the beach fill site. The placement a pipeline across the reef would have an impact on the benthic community. Potential impacts include: physical crushing, abrasion and shading of benthos (algae, sponges, soft coral and hard coral). It is expected that the major impact would occur to sponges, algae and soft corals, with some loss to hard corals. The actual level and extent of impact would be determined through post-construction surveys.

The substrate located within the footprint of the pipeline will be temporarily impacted by the placement of the pipeline. However, when the pipeline is removed the area will be re-exposed and new benthic populations will begin to quickly establish. Past observations during previous renourishments (Miami Beach 1994; Sunny Isles and

Miami Beach 1997; Surfside and South Miami Beach 1999) have shown that the pipeline made only occasional contact with the bottom, minimizing the impact by reducing the amount of substrate and number of benthic organisms contacting the pipeline. Post-placement inspection of the pipelines found them to be in contact with the reef only sporadically. Irregularities of the reef and the connector collars (or rings) used to connect the pipe segments, held the pipeline off the reef surface for considerable distances. In general, impacts to the bottom were much less than expected. The most severe impacts noted were to large hard coral heads having a colony diameter up to 2.0 m. The most common impact was to erect, dendroid soft corals that bordered the pipeline. These corals were abraded by the constant wave surge moving their branches against the pipeline. The actual impact was considerably less than the pre-project estimated impact. This was the result of several factors. The pre-project evaluation of the reef area over which the pipeline was to be placed provided a "minimal impact" path for the corridor. In addition, the connector rings for the pipeline segments raised substantial lengths of the pipe off the bottom (between 50 and 100 feet, dependent on localized relief). Finally, the irregularities of the reef itself served as point supports for the pipe, allowing substantial lengths of the pipeline (up to 150 to 200 feet) to remain off the bottom. Although organisms in contact with the pipe (soft corals, sponges and hard corals) were impacted, many of these were saved by the "suspended" pipeline. For the 1999 Surfside and South Miami Beach renourishment, the Corps included a requirement in the contract plan and specifications for "collars" to be placed along the pipeline at 100-foot intervals. The contractor elected to use large tractor tires which were slid over the pipeline and secured in place by pieces of chain that were passed through the side-wall of the tire and attached to "eyes" welded to the exterior of the pipe. Underwater surveys of the pipeline indicated that the tires were successful in holding the pipe off the bottom to a much greater extent than seen in previous projects.

Any impacts to the first reef from placing the pipeline will be appropriately mitigated. The preferred mitigation program would provide for "in-kind" mitigation. For the proposed project this would mean providing relatively low relief shallow water habitat composed of limerock or carbonate based reef materials and placed as close to the impacted area as possible. Currently there are two reef components in use that would satisfy the preferred material conditions. One is limerock boulders and the other is prefabricated modules composed of pre-cast concrete culvert, with limerock grouted to the exterior surface. The prefabricated modules were used to mitigate for the 1997 Sunny Isles and Miami Beach project and the 1999 Surfside and South Miami Beach project. A mitigation plan specific to this project would be developed in coordination with FDEP, DERM, and the Corps.

Fish are a highly motile group of organisms. During dredging most fish species will avoid the dredge area and quickly return upon dredging completion. No long-term impacts are expected to fish communities inhabiting the borrow area. The rock disposal area should provide a substrate that will act as an artificial reef and be beneficial to fish. Many gamefish species, both juveniles and adults, are associated with these areas. Hardgrounds generally display increased productivity compared to sand bottoms.

4.4.4 DISTANT DOMESTIC AND UPLAND SAND SOURCES

The use of any of these sand sources would not have any of the adverse affects on the local hardground communities that would be associated with the dredging of an offshore borrow area. However, using other offshore sources would involve dredging at the location of the source of sand. The impacts of dredging at alternate sites cannot be predicted, not knowing location of the area(s) that would be dredged or the types of habitats present. It is expected that any hardground that might be present would be avoided to the extent practicable and that unavoidable impacts would be mitigated. Using an alternate offshore source would require pumping the material to the beach from the transport vessel. This would also be required if upland sand were barged to the project area and trucks were not used to haul the material to the beach. Both these options would have the same impacts to the nearshore reef community (from pipeline placement) as discussed for the borrow areas south of Government Cut in Section 4.4.3.

4.4.5 NO ACTION ALTERNATIVE (STATUS QUO)

With the no action alternative, none of the impacts associated with dredging an offshore borrow area would occur.

4.5 ESSENTIAL FISH HABITAT

Impacts to EFH from the proposed project are discussed in detail in Section 4.4 and 4.7 of this EA.

Proper controls and procedures (buffer zones, buoys, real-time positioning, GPS, etc.) will be implemented to avoid mechanical damage to hardbottom communities adjacent to the ebb shoal borrow area. In addition, a monitoring program would be conducted to look for signs of stress or impact related to the construction activities before non-reversible impacts occur. With these precautions in place, no significant impact to the nearshore hardbottom communities adjacent to the ebb shoal borrow area are expected.

There will also be temporary turbidity impacts to the water column from dredging and beach fill activities in the vicinity of the borrow area and beach fill site. Turbidity is not expected to exceed the State standard of 29 NTU's above background.

4.6 COASTAL BARRIER RESOURCES

The purpose of the Coastal Barrier Resources Act is to minimize the loss of human life, wasteful expenditure of Federal moneys; and the damage to fish, wildlife, and other resources associated with the coastal barriers along the Atlantic coast by restricting future Federal expenditures and financial assistance, which have the effect of encouraging development of these coastal barriers. There are no designated Coastal Barrier Resource Act Units located within or adjacent to the project area.

4.7 WATER QUALITY

The proposed action would cause temporary increases in turbidity at borrow area and beach disposal sites. The State of Florida water quality regulations require that water quality standards not be violated during dredging operations. The standards state that turbidity outside the mixing zone shall not exceed 29 NTU's above background. Results from turbidity monitoring at previous beach nourishment projects have shown that the turbidity did not exceed the standard. Various protective measures and monitoring programs would be conducted during construction to ensure compliance with state water quality criteria. Should turbidity exceed State water quality standards as determined by monitoring, the contractor would be required to cease work until conditions returned to normal. The proposed action has been evaluated in accordance with Section 404 of the Clean Water Act and a 404(b) evaluation report has been included as Appendix A to this EA. The use of other submerged borrow sites would have similar turbidity impacts on water quality as using the proposed borrow area. Use of upland sources would not have the impacts associated with dredging an offshore borrow area, but would have the same impact along the beach fill area.

4.8 HAZARDOUS, TOXIC, AND RADIOACTIVE WASTE

There are no hazardous, toxic, or radioactive waste sites or producers in the project area that would be affected as a result of the preferred alternative. No impacts associated with the disturbance of such sites are anticipated from either the recommended or no-action alternatives. However, use of previously uninvestigated borrow sources would require examination for potential problems with harmful substances. This would involve examination of recorded spills and a "Preliminary Assessment Screen". If these indicate a potential for contamination, we would either try to avoid the potential contamination, look for another site, or consider remediation.

With the use of dredging and construction equipment in the in the areas around the borrow and beach fill sites, there is the potential for hydrocarbon spills or other effluent releases. However, the likelihood of significant accidents and releases of this sort is very remote. The contract specifications will require the contractor to develop accident and spill prevention

plans. The no-action alternative should not allow conditions to develop that would increase accidents or releases of this sort.

4.9 AIR QUALITY

Direct emissions from the proposed action would be confined to exhaust emissions of labor transport equipment (land and water vehicles), and construction equipment (dredge barges), and likely well under the *de minimus* levels for ozone non-attainment areas as cited in 40 CFR 91.853; that is, projects implemented cannot produce total emissions greater or equal to 100 tons per year of Volatile Organic Compounds (VOCs). Any indirect increase in emissions (indirect emissions), as a result of the proposed action is beyond the control and maintenance of the USACE. Consequently, a conformity determination with the Florida State Implementation Plan is inappropriate for increases of indirect emissions from the proposed action. As with the proposed action and alternatives, the no-action alternative will see continued development, which may cause marginal adverse impacts to air quality. The extent of these impacts, however, is difficult to predict.

4.10 NOISE

With the implementation of the proposed action there would be a temporary increase in the noise level during construction. The principle noise would stem from the vicinity of the discharge point on the beach, the breakwater construction site and the dredge. Construction equipment would be properly maintained to minimize the effects of noise. Increases from the current noise levels as a result of the proposed action would be localized and minor, and limited to the time of construction. There would be no noise related impacts associated with the no-action alternative.

4.11 AESTHETICS

There would be a temporary increase in the noise level during construction. The principle noise would stem from the vicinity of the discharge point on the beach and the dredge. Construction equipment would be properly maintained to minimize the effects of noise. Increases to the current levels of noise as a result of this project would be localized and minor, and limited to the time of construction. Engine exhaust fumes would be rapidly carried away by breezes. Any temporary decrease in air quality caused by this work would be corrected once work is completed. Hundreds of feet of dredge pipe lying on the beach or just offshore would have a negative visual impact on the aesthetics of the area. This impact would only be temporary and would be removed along with the pipe at the completion of the work. The negative visual impacts of the equipment and pipe would be offset to an extent by the natural curiosity of some individuals to see what is going on and how work is progressing. There would also be a temporary increase in turbidity during construction adjacent to the point of discharge. Turbidity would return to normal levels once construction activities

cease. Once completed the proposed project would result in an overall improved aesthetic quality. The placement of sand on the beach would restore the natural appearance of the shore. With the no-action alternative, the shoreline would continue to erode. This would result in the loss of existing the shoreline, which would reduce the visual aesthetics of the area.

4.12 RECREATION

During nourishment activities, the use of the beach in the vicinity of construction would drop or be restricted temporarily. Use of the beach in the immediate area of the discharge pipe and equipment would be restricted for public safety. Noise from the heavy equipment needed to spread and smooth the sand would disturb some users as well. Many visitors would seek quieter areas for sunbathing or swimming. As portions of the renourished beaches come available, use by the general public would increase once more. After nourishment of the beach, use by the general public and those who stay at the condominiums and hotels would return to pre-erosion activity levels. The general public would be more inclined to use these beaches rather than by-passing them for others with more sand above the high tide line. There would be a temporary adverse effect on recreational fishing in the immediate area of beach fill operations and at the borrow area due to construction activities and turbidity. Fishing would not be affected outside the area of immediate construction. Nearshore snorkeling, and SCUBA diving activities may also be impacted by increased turbidity during construction activities and shortly thereafter. Long-term adverse impacts to these water activities are not anticipated. Boat operations may be detoured during construction activities; however, the extent of these detours and time frame of operations render these impacts insignificant. With the no-action alternative, the shoreline would continue to erode. This would eventually reduce the amount of beach available for recreation and would result in the degradation or loss of shorefront property thus, adversely impacting beach recreational opportunities within the area. There would be no construction related impacts to fishing, snorkeling and SCUBA diving with the no-action plan.

4.13 HISTORIC PROPERTIES

As stated previously, archival research and field investigations were conducted for the ebb shoal borrow area proposed for this project. Five magnetic anomalies were identified during the survey. Each anomaly was determined to be modern debris and not a potentially significant cultural resource. A report describing these investigations was coordinated with the SHPO. In a letter dated November 18, 1997, the SHPO concurred with the Jacksonville District's no effect determination for the anomalies in the vicinity of the borrow area

4.14 ENERGY REQUIREMENTS AND CONSERVATION

The energy requirements for this construction activity would be confined to fuel for the dredge, labor

transportation, and other construction equipment. The expenditure of energy would be much less using the proposed ebb shoal borrow area than obtaining material from other sources described in the alternatives section. For example, obtaining sand from the SGC-EXT-2 borrow area or other distant sources would require the use of more energy to transport the sand for beach fill. The use of upland sand would most likely require the expenditure of additional energy to perform repairs to local roads and highways damaged by trucks hauling material to the beach. The no-action alternative would allow conditions to develop that may endanger coastal property from storm surges and wave erosion during future storm events. On-site preventive measures and post clean-up under the no-action alternative would likely demand greater energy than that required of the proposed action.

4.15 NATURAL OR DEPLETABLE RESOURCES

In this case, the beach quality sand used to construct the project is the depletable resource. Using sand from the proposed borrow area would temporarily deplete the sand source from the areas dredged at that site. Eventually the sand will be redistributed over nearshore areas. However, the borrow area is located in the active ebb shoal for Baker's Haulover Inlet and therefore, would recover over time. The gasoline and diesel fuel used by the dredge and other construction equipment is also a depletable resource.

4.16 CUMULATIVE IMPACTS

Cumulative impact is the impact on the environment, which results from the incremental impact of the action when added to other past, present, and reasonably foreseeable future actions (40 CFR 1508.7). The use of sand from the proposed borrow area will deplete the area of sand and species of relatively non-motile infaunal invertebrates (mollusks). However, many of those species that are not able to escape the construction area are expected to recolonize after project completion. The proposed action would result in long-term benefits, which should outweigh any short-term environmental losses. The cumulative impact of shore protection projects along the Florida coast has been to restore and maintain many beaches which otherwise would have experienced severe erosion or would have totally disappeared. In addition, these activities have reduced property damage and helped maintain property value.

4.17 IRREVERSIBLE AND IRRETRIEVABLE COMMITMENT OF RESOURCES

4.17.1 IRREVERSIBLE

An irreversible commitment of resources is one in which the ability to use and/or enjoy the resource is lost forever. One example of an irreversible commitment might be the mining of a mineral resource. The energy and fuel used during construction would be an irreversible commitment of resources.

4.17.2 IRRETRIEVABLE

An irretrievable commitment of resources is one in which, due to decisions to manage the resource for another purpose, opportunities to use or enjoy the resource as they presently exist are lost for a period of time. An example of an irretrievable loss might be where a type of vegetation is lost due to road construction. Benthic organisms within the borrow area and beach fill area that would be eliminated during construction would be irretrievably lost for a period of time. However, the high rate of repopulation expected from these organisms reduces the significance of the loss.

4.18 UNAVOIDABLE ADVERSE ENVIRONMENTAL EFFECTS

Species of relatively non-motile infaunal invertebrates that inhabit the borrow area will unavoidably be lost during dredging. Those species that are not able to escape the construction area are expected to recolonize after project completion. There would be

an unavoidable reduction in water clarity and increased turbidity and sedimentation. This would be limited to the immediate areas of dredging and beach fill operations. This impact will be temporary and should disappear shortly after construction activities cease.

4.19 LOCAL SHORT-TERM USES AND MAINTENANCE/ENHANCEMENT OF LONG-TERM PRODUCTIVITY

We recognize that protection of the shoreline is a continual effort. No acceptable and permanent one-time fix has been identified. Using periodic renourishment is an ongoing effort. Renourishment efforts have a temporary and short-term impact on the biological resources on and near the shore. Removal of material from offshore borrow sites has a long-term impact on the nature of the borrow site. However, these impacts are not substantial since there are no special resources within the borrow site and some resources remain after dredging.

5. ENVIRONMENTAL COMMITMENTS

The U.S. Army Corps of Engineers and contractors commit to avoiding, minimizing or mitigating for adverse effects during construction activities by including the following commitments in the contract specifications:

(1) Inform contractor personnel of the potential presence of sea turtles and manatees in the project area, their endangered status, the need for precautionary measures, and the Endangered Species Act prohibition on taking sea turtles, manatees and other threatened or endangered species.

(2) Take precautions during construction activities to insure the safety of the manatee. To insure the contractor and his personnel are aware of the potential presence of the manatee in the project area, their endangered status, and the need for precautionary measures, the contract specifications would include the standard protection clauses concerning manatees. The contractor would instruct all personnel associated with the construction of the project about the presence of manatees in the area and the need to avoid collisions with manatees. All vessels associated with the project shall operate at 'no wake' speeds at all times while in shallow waters, or channels, where the draft of the boat provides less than three feet clearance of the bottom. Boats used to transport personnel shall be shallow draft vessels, preferably of the light-displacement category, where navigational safety permits. Vessels transporting personnel between the landing and any workboat shall follow routes of deep water to the extent possible. Shore crews or personnel assigned to the disposal site for the workshift shall use upland road access if available. All personnel would be advised that there are civil and criminal penalties for harming, harassing, or killing manatees, which are protected under the Endangered Species Act and the Marine Mammal Protection Act. The contractor shall be held responsible for any manatee harmed, harassed, or killed as a result of the construction of the project. If a manatee is sighted within 100 yards of the dredging area, appropriate safeguards would be taken, including suspension of dredging, if necessary, to avoid injury to manatees. The contractor shall keep a log of all sightings, collision, injuries, or killings of manatees during the contract period. Any manatee deaths or injuries will be immediately reported to the Corps of Engineers and the USFWS (Vero Beach Office).

(3) To minimize adverse impacts to sea turtles the Corps will implement the terms and conditions as stated in the NMFS Regional Biological Opinion for hopper dredging on the Southeast Atlantic Coast as amended on September 25, 1997. The Corps will also implement all the terms and conditions as outlined in the USFWS Biological Opinion issued on May 17, 2002 (Appendix C). Measures to minimize adverse effects to sea turtles are summarized below:

a. Nourished beaches would be plowed to a depth of at least 36 inches within one week following the completion of the entire beach nourishment (or sooner on completed sections) if sand compaction is greater than 500 cone penetrometer units.

b. Nourished beaches would be checked for compaction every 500 feet along the project area. One station shall be at the seaward edge of the dune/bulkhead line (when material is placed in this area); one station shall be located between the dune line and the high water line; and one station shall be located just landward of the mean high water line. At each station three readings would be made at 6, 12, and 18-inch depths three time (three replicates). If any two or more adjacent stations have compaction at the same depth greater than 500 cone penetrometer units, the area would be plowed to a depth of at least 36 inches immediately prior to April 1. This process would be completed for three consecutive years following project completion.

c. Nest relocation activities must begin 65 days prior to nourishment activities which occur within the nesting and hatching season (April 1 - November 30) or by April 1, whichever is later. Nest surveys and relocations shall continue through the end of the project or September 30, whichever is earlier.

d. Nest surveys and relocations would be conducted by personnel with prior experience and training in nest survey and relocation procedures, and with a valid permit from the Florida Fish and Wildlife Conservation Commission (FWC) for handling sea turtles and relocating nests.

e. Nests would be relocated between sunrise and 9 a.m. each day, and the relocation would be to a nearby hatchery in a secure setting where artificial lighting would not conflict with hatchling orientation.

f. In the event a turtle nest is dug up by beach construction activities, the contractor shall immediately notify the FWC permitted individual responsible for nest relocation so that the nest can be moved to the beach hatchery.

g. A report describing the actions taken to implement the terms and conditions shall be submitted to the USFWS within 60 days of completion of the proposed work for each year when activity has occurred. The report shall include the dates of actual construction activities, names and qualifications of personnel involved in nest surveys and relocation activities, descriptions and locations of the hatcheries, nest survey and relocation results and hatching success of the nests.

h. Nourished beaches would be surveyed for escarpments immediately after construction and prior to April 1, for 3 subsequent years. Any escarpments that exceed 18 inches in height and 100 feet length would be leveled by April 1.

i. Measures will be taken to reduce night time beach lighting including: eliminating extraneous lighting to an amount necessary for safe operations and safety of personnel.

The following would apply if a hopper dredge were to be used:

j. The drag arms of the hopper dredge will be fitted with a rigid sea turtle deflector draghead, and modified as necessary to eliminate sites of inadvertent entrainment of sea turtles.

k. The inflow to the hoppers will be screened as close to 100% as possible. There will be 100% observer coverage to monitor the screens for evidence of turtle take.

l. To minimize the potential for sea turtle entrainment, the dredge pumps would be shut down before the draghead is lifted off the bottom and would not be turned on until the draghead is placed on the bottom. NOTE: If the actual dredging operation has difficulty with this procedure, the Corps reserves the right to re-consult with NMFS to delete or modify this requirement.

(4) Monitor turbidity at both the dredging and discharge sites. Should monitoring reveal turbidity levels above State standards, outside the allowable mixing zone, work would be suspended until turbidity levels return to within those standards.

(5) Precautions would be implemented during construction to minimize potential impacts to the nearshore hardbottom communities adjacent to the ebb shoal borrow area. A buffer zone of at least 400 feet has been established between the borrow area and any hardbottom habitat.

(6) A sedimentation and biological monitoring program to assess possible impacts of dredging operations to reef and live-bottom habitats near the borrow area would be conducted. A physical and biological monitoring program is included as Appendix E to this EA.

6. COMPLIANCE WITH ENVIRONMENTAL REQUIREMENTS

6.1 NATIONAL ENVIRONMENTAL POLICY ACT OF 1969

Environmental information on the project has been compiled and a Draft Environmental Impact Statement, dated March 2002 was prepared and circulated to the appropriate Federal, State and local agencies and other interested parties for their review and comment. The project is in compliance with the National Environmental Policy Act.

6.2 ENDANGERED SPECIES ACT OF 1973

In a letter dated March 1, 2000 the Corps submitted project information to the National Marine Fisheries Service (NMFS) pursuant to Section 7 of the Endangered Species Act. In the letter the Corps had determined that the proposed project activities were covered under their Regional Biological Opinion (RBO) on hopper dredging along the Southeast Atlantic Coast as amended on September 25, 1997. In a letter dated March 13, 2000 the NMFS concurred with that determination. The Corps has determined the proposed project may affect but is not likely to adversely affect sea turtles under the jurisdiction of the U.S. Fish and Wildlife Service (USFWS). In a letter dated February 29, 2000 the Corps determined that the USFWS Programmatic Biological Opinion, issued on October 24, 1996, for Region III of the Coast of Florida Erosion and Storm Effects Study applied to Haulover Beach Park project. The Corps has also determined that the changes to the "Reasonable and Prudent Measures" and "Terms and Conditions" as stated in USFWS letter dated October 4, 2000 also apply. The USFWS issued a Biological Opinion (BO) for this project on May 17, 2002. Refer to Appendix C for correspondence and the USFWS BO. The project has been fully coordinated under the Endangered Species Act and therefore, is in full compliance with the Act.

6.3 FISH AND WILDLIFE COORDINATION ACT OF 1958

This project has been coordinated with the U.S. Fish and Wildlife Service (USFWS). Information concerning the project design, borrow area location, geotechnical data on the fill material, dredging methodology and the location of hardbottom communities has been provided to the USFWS. Several previous fish and wildlife studies have been conducted by the USFWS for the Dade County BEC & HP Project, including the ebb shoal borrow area proposed for the renourishment at Haulover Beach Park. (USFWS, 1997a, 1997b, 2001). The recommendations of the USFWS have been given full consideration in developing the design of this project. This project is in full compliance with the Act.

6.4 NATIONAL HISTORIC PRESERVATION ACT OF 1966 (INTER ALIA)

(PL 89-665, the Archeology and Historic Preservation Act (PL 93-291), and executive order 11593) Archival research, field investigations, and consultation with the Florida State Historic Preservation Officer (SHPO), have been conducted in accordance with the National Historic Preservation Act, as amended; the Archeological and Historic Preservation Act, as amended and Executive Order 11593. Refer to Section 4.13 for results of SHPO consultation. The project will not affect historic properties included in or eligible for inclusion in the National Register of Historic places. The project is in compliance with each of these Federal laws.

6.5 CLEAN WATER ACT OF 1972

The project is in compliance with this Act. On July 27, 2001 the Florida Department of Environmental Protection issued Water Quality Certification (permit no. 0128781-001-JC. All State water quality standards would be met. A Section 404(b) evaluation is included in this report as Appendix A. A public notice was issued on February 3, 2000 that will satisfy the requirements of Section 404 of the Clean Water Act.

6.6 CLEAN AIR ACT OF 1972

Refer to Section 4.9 in the EA for a discussion on the compliance with the Clean Air Act General Conformity Rules. No air quality permits would be required for this project. This project has been coordinated with U.S. Environmental Protection Agency (EPA) and is in compliance with Section 309 of the Act. The draft EA was forwarded to EPA for their review. Refer to EPA letter dated March 26, 2002 in Appendix C.

6.7 COASTAL ZONE MANAGEMENT ACT OF 1972

A federal consistency determination in accordance with 15 CFR 930 Subpart C is included in this report as Appendix B. State consistency review was conducted during the coordination of the draft EA. With the issuance of the State Water Quality Certification the project is consistent with the Florida Coastal Zone Management Program.

6.8 FARMLAND PROTECTION POLICY ACT OF 1981

No prime or unique farmland would be impacted by implementation of this project. This act is not applicable.

6.9 WILD AND SCENIC RIVER ACT OF 1968

No designated Wild and Scenic river reaches would be affected by project related activities. This act is not applicable.

6.10 MARINE MAMMAL PROTECTION ACT OF 1972

Incorporation of the safe guards used to protect threatened or endangered species during dredging and disposal operations would also protect any marine mammals in the area, therefore, this project is in compliance with the Act.

6.11 ESTUARY PROTECTION ACT OF 1968

No designated estuary would be affected by project activities. This act is not applicable.

6.12 FEDERAL WATER PROJECT RECREATION ACT

The principles of the Federal Water Project Recreation Act, (Public Law 89-72) as amended, have been fulfilled by complying with the recreation cost sharing criteria as outlined in Section 2 (a), paragraph (2). Another area of compliance includes the public beach access requirement on which the renourishment project hinges (Section 1, (b)).

6.13 FISHERY CONSERVATION AND MANAGEMENT ACT OF 1976

The project has been coordinated with the National Marine Fisheries Service (NMFS) and is in compliance with the act (refer to correspondence in Appendix C from NMFS).

6.14 SUBMERGED LANDS ACT OF 1953

The project would occur on submerged lands of the State of Florida. The project has been coordinated with the State and is in compliance with the act.

6.15 COASTAL BARRIER RESOURCES ACT & COASTAL BARRIER IMPROVEMENT ACT OF 1990

There are no designated coastal barrier resources in the project area that would be affected by this project. These acts are not applicable.

6.16 RIVERS AND HARBORS ACT OF 1899

The proposed work would not obstruct navigable waters of the United States. The proposed action has been subject to the public notice (February 3, 2000), with opportunity for a public hearing, and other evaluations normally conducted for activities subject to the act. The project is in full compliance.

6.17 ANADROMOUS FISH CONSERVATION ACT

Anadromous fish species would not be affected. The project has been coordinated with the National Marine Fisheries Service and is in compliance with the act.

6.18 MIGRATORY BIRD TREATY ACT AND MIGRATORY BIRD CONSERVATION ACT

No migratory birds would be affected by project activities. The project is in compliance with these acts.

6.19 MARINE PROTECTION, RESEARCH AND SANCTUARIES ACT

The term "dumping" as defined in the Act (33 U.S.C. 1402)(f) does not apply to the disposal of material for beach nourishment. Therefore, the Marine Protection, Research and Sanctuaries Act does not apply to this project. The disposal activities addressed in this EA have been evaluated under Section 404 of the Clean Water Act.

6.20 MAGNUSON-STEVENSON FISHERY CONSERVATION AND MANAGEMENT ACT

This Act requires the preparation of an Essential Fish Habitat (EFH) Assessment and coordination with NMFS. The EFH Assessment was integrated within the EA and was coordinated with NMFS during the coordination of the draft EA. Refer to NMFS letter dated April 4, 2002 and the Corps response dated May 1, 2002 in Appendix C.

6.21 E.O. 11990, PROTECTION OF WETLANDS

No wetlands would be affected by project activities. This project is in compliance with the goals of this Executive Order.

6.22 E.O. 11988, FLOOD PLAIN MANAGEMENT

The project is in the base flood plain (100-year flood) and has been evaluated in accordance with this Executive Order. Refer to Dade County Beaches, Florida, Beach Erosion Control and Hurricane Surge Protection, General Design Memorandum, Phase I, 1974. Project is in compliance.

6.23 E.O. 12898, ENVIRONMENTAL JUSTICE

The proposed action would not result in adverse human health or environmental effects, nor would the activity impact subsistence consumption of fish or wildlife. Project is in compliance.

6.24 E.O. 13089, CORAL REEF PROTECTION

The proposed action may affect U.S. coral reef ecosystems as defined in the Executive Order. Precautions would be implemented during construction to minimize impacts. Project is in compliance.

7. LIST OF PREPARERS

7.1 PREPARERS

This Environmental Assessment was prepared by the following personnel:

Preparer	Discipline	Role
Michael Dupes	Biology	Principal Writer
Thomas Birchett	Archeology	Historic Properties
Doug Rosen	Coastal Geology	Geotechnical Analysis

7.2 REVIEWERS

This Environmental Assessment was reviewed by Kenneth Dugger, Acting Chief, Environmental Branch.

8. PUBLIC INVOLVEMENT

8.1 SCOPING AND DRAFT EA

Scoping for the proposed action was initiated by a Public Notice dated February 3, 2000. The Public Notice was distributed to the appropriate Federal, State and Local agencies, appropriate city and county officials, and other parties known to be interested in the project. Copies of the Public Notice, the list of addressees used to distribute the notice, and letters of response are included in Appendix C, Pertinent Correspondence. A Notice of Availability (dated March 7, 2002) of the draft EA was prepared and sent to appropriate Federal, State and Local agencies, appropriate city and county officials, and other interested parties.

8.2 AGENCY COORDINATION

The draft EA was coordinated with the following agencies: U.S. Fish and Wildlife Service, National Marine Fisheries Service, U.S. Environmental Protection Agency, Florida State Clearinghouse,

Florida State Historic Preservation Officer (SHPO), Florida Fish and Wildlife Conservation Commission, and the Florida Department of Environmental Protection.

8.3 COMMENTS RECEIVED

Letters of comment on the draft EA were received from the U.S. Fish and Wildlife Service, National Marine Fisheries Service, U.S. Environmental Protection Agency, Florida State Clearinghouse, Florida State Historic Preservation Officer (SHPO), Florida Fish and Wildlife Conservation Commission, the Florida Department of Environmental Protection and the South Florida Regional Planning Council. Copies of these letters can be found in Appendix C.

REFERENCES

- Barry A. Vittor & Associates, Inc. 1984. Benthic Macroinfaunal Analysis of the Port Everglades, Florida Ocean Dredge Material Disposal Site Survey. Final report to JRB Associates, McLean, Virginia. 15 pp.
- Blair, S., and B. Flynn. 1988. Sunny Isles Beach Restoration Project: Mechanical Damage to the Reefs Adjacent to the Borrow Area. Metro-Dade DERM Technical Report 88-14.
- Blair, S., and B. Flynn. 1989. Biological Monitoring of Hardbottom Communities off Dade County Florida: Community Description. In *Diving for Science 1989, Proceeding of the American Academy of Underwater Science, Ninth Annual Scientific Diving Symposium* (Eds. Lang and Japp). Costa Mesa, California.
- Blair, S., B. Flynn, T. McIntosh, L. Hefty. 1990. Environmental Impacts of the 1990 Bal Harbor Beach Renourishment Project: Mechanical and Sedimentation Impact on Hard-Bottom Areas Adjacent to the Borrow Area. Metro-Dade DERM Technical Report 90-15.
- Bowen, P.R., and G.A. Marsh. 1988. "Benthic Faunal Colonization of an Offshore Borrow Pit in Southeastern Florida," Miscellaneous Paper D-88-5, U.S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi.
- Carr, A., A. Meylan, J. Mortimer, K. Bjorndal, and T. Carr. 1982. Surveys of sea turtle populations and habitats in the Western Atlantic. NOAA Technical Memorandum NMFS-SEFC-91. 91 pp.
- Coastal Planning & Engineering, Inc. August 1989. North Boca Raton Beach Restoration Project Preconstruction Environmental Monitoring. Vols. I and II. Prepared for City of Boca Raton, Florida. Coastal Planning & Engineering: Boca Raton, Florida.
- Continental Shelf Associates, Inc. 1993. Coast of Florida Erosion and Storm Effects Study, Region III: Mapping and Classification of Hard Bottom Areas in Coastal Waters off Palm Beach, Broward, and Dade Counties. Final report for the U.S. Army Corps of Engineers, Jacksonville District, Jacksonville, Florida. Three individual county reports, 30 pp. each.
- Continental Shelf Associates, Inc. 1984. Environmental Assessment of the Palm Beach County Erosion Control Program: Phase I: Ocean Ridge. Final report for the Palm Beach County Board of County Commissioners. 110 pp.
- Continental Shelf Associates, Inc. 1985. Environmental Assessment of the Palm Beach County Erosion Control Program: Phase II: North Boca Raton. Final report for the Palm Beach County Board of County Commissioners. 114 pp.
- Continental Shelf Associates, Inc. 1987. Environmental Assessment of the Palm Beach County Erosion Control Program: Phase III: Jupiter/Tequesta. Final report for the Palm Beach County Board of County Commissioners. 50 pp.
- Courtenay, W. R., Jr., D. J. Herrema, M. J. Thompson, W. P. Azzinaro, and J. van Montfrans. 1974. Ecological Monitoring of Beach Erosion Control Projects, Broward County, Florida, and Adjacent Areas. Technical Memorandum 41, USACE, Ft. Belvoir, Virginia. 88 pp.
- Cutler, J.K., and S. Mahadevan. 1982. Long-Term Effects of Beach Nourishment on the Benthic Fauna of Panama City, Florida. U.S. Army Corps of Engineers, Coastal Engineering Research Center. Misc. Report No. 82-2.
- Deis, D.R., K.D. Spring, A.D. Hart. 1992. Captiva Beach Restoration Project Biological Monitoring Program. Proceedings of the National Conference on Beach Preservation Technology, 1992.

Dickerson, D.D., and D.A. Nelson. 1989. Beachfront Lighting Issues Regarding Sea Turtles. Pp 135-141 in Proceedings of Beach Preservation Technology '89 held February 22-24, 1989 at Tampa Florida. Florida Shore and Beach Preservation Association.

Dodge, Richard E., Steven Hess, and Charles Messing. January 1991. Final Report: Biological Monitoring of the John U. Lloyd Beach Renourishment: 1989. Prepared for Broward County Board of County Commissioners Erosion Prevention District of the Office of Natural Resource Protection. NOVA University Oceanographic Center: Dania, Florida. 62 pp. plus appendices.

Dompe, P. E. and D. M. Haynes. 1993. "Turbidity Data: Hollywood Beach, Florida, January 1990 to April 1992." Coastal & Oceanographic Engineering Department, University of Florida: Gainesville, Fla. UFL/COEL - 93/002.

Duane, D. B., and E. P. Meisburger. 1969. Geomorphology and Sediments of the Nearshore Continental Shelf, Miami to Palm Beach, Florida. USACOE Coastal Engineering Center, Technical Memorandum No. 29. 47 pp.

Florida Atlantic University and Continental Shelf Associates, Inc. 1994. An Assessment of the Effects of Recurrent *Codium isthmocladum* Blooms on the Reefs and Reef Fish Populations of Palm Beach and Northern Broward Counties, Florida. Final report for the Florida Marine Fisheries Commission, Tallahassee, Florida. 51 pp. plus appendices.

Flynn, B. 1992. Beach Nourishment, Sea Turtle Nesting, and Nest Relocation in Dade County, Florida. Proceedings of the 5th Annual National Conference on Beach Preservation Technology, St Petersburg, Florida 1992. pp 381-394.

Goldberg, W.M. 1985. Long Term Effects of Beach Restoration in Broward County, Florida, A Three Year Overview. Part I: Macrobenthic Community Analysis. Coral Reef Associates, Inc./ Florida International University, Miami, Florida. 20 pp.

Goldberg, W.M., P.A. McLaughlin, and S. Mehadevan. 1985. Long Term Effects of Beach Restoration in Broward County, Florida, A Three Year Overview. Part II: Infaunal Community Analysis. Coral Reef Associates, Inc./ Florida International University, Miami, Florida./Mote Marine Laboratory, Sarasota, Florida. 31 pp.

Goldberg, W. M. 1970. Some Aspects of the Ecology of the Reefs off Palm Beach County, Florida, with Emphasis on the Gorgonacea and Their Bathymetric Distribution. M.S. Thesis, Florida Atlantic University. 108 pp.

Goldberg, W. 1973. "The Ecology of the Coral-Octocoral Communities off the Southeast Florida Coast: Geomorphology, Species Composition, and Zonation." *Bulletin of Marine Science* 23:465-488.

Gozelany, J.F., and W.G. Nelson. 1987. The Effects of Beach Nourishment on the Benthos of a Sub-tropical Florida Beach. *Marine Environmental Research*. 21:75-94.

Herrema, D. J. 1974. Marine and Brackish Water Fishes of Southern Palm Beach and Northern Broward Counties, Florida. M.S. Thesis, Florida Atlantic University. 257 pp.

Jaap, W. C. 1984. The Ecology of the South Florida Coral Reefs: A Community Profile. U.S. Fish and Wildlife Service Report FWS/OBS - 82/08. 138 pp.

Lighty, R. G., I. G. MacIntyre, and R. Stuckenrath. 1978. "Submerged Early Holocene Barrier Reef South-east Florida Shelf." *Nature (London)* 276 (5683):59-60.

Lutz, P.L., A.A. Schulman, and S.L. Shaw. 1991. Fisher Island Sea Turtle Project Annual Report 1991. Rosenstiel School of Marine & Atmospheric Science, Division of Marine Biology and Fisheries, University of Miami.

Marsh, G. A., P. R. Bowen, D. R. Deis, D. B. Turbeville, and W. R. Courtenay. 1980. "Evaluation of Benthic Communities Adjacent to a Restored Beach, Hallandale (Broward County), Florida," Vol. II, Ecological Evaluation of a Beach Nourishment Project at Hallandale (Broward County), Florida, MR 80-1(II), U.S. Army Corps of Engineers, Coastal Engineering Research Center.

Marszalek, D. S. 1978. Professional Engineering Services for Surveying and Monitoring of Marine Hardground Communities in Dade County, Florida. Final report for the USACE, Jacksonville District. Contract No. DACW17-77-C-0036.

Marszalek, D. S., and D. L. Taylor. 1977. Professional Engineering Services for Surveying and Monitoring of Marine Hardground Communities in Dade County, Florida. Initial report for the USACE, Jacksonville District. Contract No. DACW17-77-C-0036.

Meylan, A., B. Schroeder, and A. Mosier. 1995. Sea Turtle Nesting Activity in the State of Florida 1979-1992. Florida Marine Research Publications, Number 52. State of Florida Department of Environmental Protection, Florida Marine Research Institute. St. Petersburg, Fl. 51pp.

Modde, T. 1980. "Growth and Residency of Juvenile Fishes Within a Surf Zone Habitat in the Gulf of Mexico." Gulf Research Report 6:377-385.

Modde, T., and S. T. Ross. 1981. "Seasonality of Fishes Occupying a Surf Zone Habitat in the Northern Gulf of Mexico." Fisheries Bulletin 78:911-922.

Nelson, D. A. 1987. The use of tilling to soften nourished beach sand consistency for nesting sea turtles. Unpublished draft for U.S. Army Corps of Engineers, Jacksonville District.

Nelson, D. A., Mauck, K., and Fletemeyer, J. 1987. Physical Effects of Beach Nourishment on Sea Turtle Nesting, Delray Beach, Florida, Technical Report EL-87-15, US Army Engineer Waterways Experiment Station, Vicksburg, Mississippi.

Nelson, D. A., and D. D. Dickerson. 1989a. Effects of Beach Nourishment on Sea Turtles. In 1989 Proceedings of the Florida Shore and Beach Conference, Tampa Florida.

Nelson D. A., S. M. Blair, R. Cheeks, P. L. Lutz, S. L. Milton, and T. S. Gross. 1996. Evaluation of Alternative Beach Nourishment Sands as Loggerhead Sea Turtle Nesting Substrates.

Nelson, W.G. 1985. Guidelines for Beach Restoration Projects. Part I - Biological. Florida Sea Grant College. SGC-76. 66 pp.

Peters, D. J., and W. G. Nelson. 1987. "The Seasonality and Spatial Patterns of Juvenile Surf Fishes of the Florida East Coast." Florida Scientist 50(2):85-99.

Raymond, B., and A. Antonius. 1977. Biological Monitoring Project of the John U. Lloyd Beach Restoration Project. Final report for Broward County Erosion Prevention District, Broward County, Florida.

SAFMC, 1998. Habitat Plan for the South Atlantic Region: Essential Fish Habitat Requirements for Fishery Management Plans of the South Atlantic Fishery Management Council.

Smith, N. P. 1981. "Upwelling in Atlantic Shelf Waters of South Florida." Florida Scientist 45:125-138.

Smith, N. P. 1983. "Temporal and Spatial Characteristics of Summer Upwelling Along Florida's Atlantic Shelf." Journal of Physical Oceanography 13(9): 1,709-1,715.

Spring, Keith D. "A Study of Spatial and Temporal Variations in the Nearshore Macrobenthic Populations of the Central Florida East Coast." A Thesis submitted to Florida Institute of Technology, Department of Oceanography and Ocean Engineering, Bio-Environmental Oceanography. June 1981.

U.S. Army Corps of Engineers. 1974. Phase I, General Design Memorandum, Beach Erosion Control and Hurricane Protection Study, Dade County, Florida.

U.S. Army Corps of Engineers. 1975. Final Environmental Impact Statement, Beach Erosion Control and Hurricane Surge Protection Project, Dade County, Florida.

U.S. Army Corps of Engineers. 1984. Survey Report and EIS Supplement, Beach Erosion Control and Hurricane Protection Study for Dade County, Florida, North of Haulover Park.

U.S. Army Corps of Engineers. 1995. Dade County, Florida Shore Protection Project, Design Memorandum, Addendum III, North of Haulover Park (Sunny Isles) Segment.

U.S. Army Corps of Engineers. 1995. Final Environmental Assessment, Second Periodic Nourishment, Sunny Isles and Miami Beach Segments, Beach Erosion Control and Hurricane Protection Project, Dade County, Florida.

U.S. Army Corps of Engineers. 1996. Coast of Florida Erosion and Storm Effects Study, Region III, Feasibility Report with Final Environmental Impact Statement.

U.S. Army Corps of Engineers. 1997. Final Environmental Assessment, Second Periodic Nourishment, Surfside and South Miami Beach Segments, Beach Erosion Control and Hurricane Protection Project, Dade County, Florida.

U.S. Army Corps of Engineers. 1998. Final Environmental Assessment, Second Periodic Nourishment at Bal Harbour, Beach Erosion Control and Hurricane Protection Project, Dade County, Florida.

U.S. Army Corps of Engineers. 1998. Final Environmental Impact Statement, Modifications at Sunny Isles, Beach Erosion Control and Hurricane Protection Project, Dade County, Florida.

U.S. Army Corps of Engineers. 2000. Final Environmental Assessment, Renourishment at Miami Beach In the Vicinity of 63rd Street, Beach Erosion Control and Hurricane Protection Project, Dade County, Florida.

U.S. Environmental Protection Agency. 1992. Water Quality Protection Program for the Florida Keys National Marine Sanctuary: Phase I Report. Final report submitted to the Environmental Protection Agency under Work Assignment 3-225, Contract NO. 68-C8-0105 by Battelle Ocean Sciences, Duxbury, Massachusetts and Continental Shelf Associates, Inc., Jupiter, Florida.

U.S. Fish and Wildlife Service. 1997a. Fish and Wildlife Coordination Act Report, Modifications to: Sunny Isles Beach Project, Dade County, Florida. September 1997.

U.S. Fish and Wildlife Service. 1997b. Fish and Wildlife Coordination Act Report, Bal Harbour, Dade County, Florida. October 1997.

U.S. Fish and Wildlife Service. 2001. Final Fish and Wildlife Coordination Act Report, Miami-Dade County Beach Erosion Control and Hurricane Protection Project, 63rd Street Beach Renourishment, Miami Beach, Florida. February 2001.

Watts, G. P., Jr. 1993. A Submerged Cultural Resource Magnetometer Survey for Two Borrow Areas, Second Beach Renourishment, Dade County, Florida. Tidewater Atlantic Research, Inc. Washington, North Carolina.

Watts, G. P., Jr. 1996. A Magnetometer and Side Scan Borrow Area Extension, Dade County, Florida. Tidewater Atlantic Research, Inc. Washington, North Carolina.

Watts, G. P., Jr. 1997. Submerged Historic Properties Survey of Proposed Borrow Area for Dade County Shore Protection Project, Second Periodic Beach Renourishment at Bal Harbour (Draft Report). Tidewater Atlantic Research, Inc. Washington, North Carolina.

Witherington, B. E. 1991. Orientation of hatchling loggerhead sea turtles at sea off artificially lighted and dark beaches. *J. Exp. Biol. Ecol.* Vol. 149, Pp. 1-11.

Witherington, B. E. 1992. Behavioral responses of nesting sea turtles to artificial lighting. *Herpetologica* Vol. 48 No. 1 Pp. 31-39.

INDEX

—A—

Aesthetics, 22, 23
Affected Environment, 9, 13
AFFECTED ENVIRONMENT, 13
AGENCY COORDINATION, 29
Air Quality, 22, 27, 43
AIR QUALITY, 16, 22
Alternative, 9, 13, 17, 23
Alternatives, iii, 2, 9, 10, 13, 17, 23
ALTERNATIVES, 9
Alternatives Considered, iii
Archeological, 27, 42
Artificial Reef, 42

—B—

Benthic, 42
Birds, 28
Boca Raton, 15, 30
borrow area, 16, 17, 18, 23, 24
Borrow Area, 16, 17, 23, 24, 42
Buffer Zone, 17

—C—

Cementation, 17
Class III, 15
Clean Water Act, 27, 28
Coastal Barrier Resources, 28
COASTAL BARRIER RESOURCES, 15, 21
COASTAL ZONE MANAGEMENT CONSISTENCY,
41
Compaction, 17, 18
COMPARISON OF ALTERNATIVES, 10
Consultation, 27
Contamination, 16
Coordination, 27
Coral, 15, 31
 Coral reef, 14, 31
 Hard coral, 15
 Soft coral, 15
County, 1, 9, 16, 18, 42
CUMULATIVE IMPACTS, 23

—D—

De minimus, 22
DECISIONS TO BE MADE, 2
Deflector Draghead, 18
Delray Beach, 14
Dune, 13
Dunes, 42

—E—

EA, 9, 28, 29
Economic, 42
Effect, 17, 18, 23, 42, 43
Emissions, 22
Endangered, 27
ENERGY REQUIREMENTS AND CONSERVATION, 23
Enhance, 17, 43
Environmental Assessment, 2, 27
ENVIRONMENTAL COMMITMENTS, 25
ENVIRONMENTAL EFFECTS, 17
erosion, 23
Erosion, 1, 9, 23, 43

—F—

Federal, 1, 28, 42
Fish, 28, 42
Fish and Wildlife, 27
FISH AND WILDLIFE RESOURCES, 13, 18
Flood Plain, 28
Formations
 Anastasia, 14

—G—

GENERAL ENVIRONMENTAL EFFECTS, 17
Grass
 Dune panic, 13
 Sea, 13

—H—

Habitat, 17, 18, 42, 43
hardgrounds, 17, 18
Hardgrounds, 13, 14, 15, 17, 18, 32
HARDGROUNDS, 14
Hazardous, 43
HAZARDOUS, TOXIC AND RADIOACTIVE WASTE,
16
HAZARDOUS, TOXIC, AND RADIOACTIVE WASTE,
22
Historic, 27, 42
Historic Preservation, 16, 27, 42
HISTORIC PROPERTIES, 16

—I—

Impact, 17, 18, 22, 23, 24, 42, 43
Infrastructure, 42
Inlet, 14, 15
 Palm Beach, 14
IRREVERSIBLE AND IRRETRIEVABLE
COMMITMENT OF RESOURCES, 23

—J—

John U. Lloyd State Recreation Area, 31, 32

—L—

LIST OF PREPARERS, 29
LOCAL SHORT-TERM USES AND
MAINTENANCE/ENHANCEMENT OF LONG-
TERM PRODUCTIVITY, 24

—M—

Magnetic Anomaly, 16
Mitigation, 42
MITIGATION, 10

—N—

National Environmental Policy Act, 27
National Marine Fisheries Service, 28
NATURAL OR DEPLETABLE RESOURCES, 23
Nephelometric Turbidity Units (NTU), 15
Nesting, 17, 18, 42
No Action, 11, 17
Noise, 23
NOISE, 16, 22
Non-attainment, 22
Nourishment, 1, 9, 16, 17, 18, 23, 42, 43

—O—

Ocean Ridge, 15, 30
Octocoral, 15, 31
Offshore, 9, 16, 17, 18, 22
Oil, 43
Ozone, 22

—P—

PERMITS, LICENSES, AND ENTITLEMENTS, 2
Petroleum, 43
Plants
 Coconut palm, 13
 Inkberry, 13
Population, 13, 31
Preservation, 16, 27, 42
PROJECT LOCATION, 1
PROJECT NEED OR OPPORTUNITY, 1

—R—

Recreation, 15, 17, 23, 28, 43
RECREATION RESOURCES, 16
Reef, 42
RELATED ENVIRONMENTAL DOCUMENTS, 1

Relocation, 17
Renourishment, 9, 16, 17, 28, 43
Resources, 1, 10, 13, 23, 28, 42, 43, 44
Restore, 17, 22

—S—

Safety, 23, 42
Scarp, 17, 18
Scoping, 2
SCOPING AND ISSUES, 2
Sea Grass, 17, 42
Sea Turtle Nesting, 18, 42
Section 404, 27, 28
SECTION 404(B) EVALUATION, 35
Sediment, 9
SHPO, 16, 27, 42
Silt, 17
Soft bottom, 13, 14
Solid Waste, 43
State, 16, 27, 28, 42
State Historic Preservation, 16, 27, 42
Summary, iii, 11

—T—

THREATENED AND ENDANGERED SPECIES, 13, 17
Tilling, 17
Transfer, 43
Turbidity, 15, 22, 23
Turtle, 18, 42

—U—

U.S. Army Corps of Engineers, 25
U.S. Environmental Protection Agency, 27
U.S. Fish and Wildlife Service, 27
UNAVOIDABLE ADVERSE ENVIRONMENTAL
EFFECTS, 24
Unique, 27, 42
Upland, 17, 18, 23

—V—

Vegetation, 17, 24
VEGETATION, 13, 17

—W—

Water quality, 15
Water Quality, 33
WATER QUALITY, 15
Water Quality Certification, 43
Water Resources, 1, 43
Wildlife, 42

APPENDIX A - SECTION 404(B) EVALUATION

SECTION 404(b) EVALUATION

**SECOND PERIODIC RENOURISHMENT
AT HAULOVER BEACH PARK
DADE COUNTY BEACH EROSION CONTROL
AND HURRICANE PROTECTION PROJECT
DADE COUNTY, FLORIDA**

I. Project Description

a. Location. The project is located in Dade County on the southeast coast of Florida. Haulover Beach Park is a County park bounded by Bakers Haulover Inlet to the south and the town of Sunny Isles to the north. The proposed work will be performed as a part of the Dade County Beach Erosion Control and Hurricane Protection Project. Refer to the project location map, figure 1, in the Environmental Assessment (EA).

b. General Description. The placement of about 114,000 cubic yards of material will be required along the beachfront at Haulover Beach Park. The fill will extend from the border with Sunny Isles southward approximately 2,600 feet. The construction berm width is 120 feet from the ECL at an elevation of +9 feet mean low water (MLW), with a construction tolerance of +/- 0.5 feet. The front slope of the fill will be 1 vertical on 10 horizontal (refer to figure 2, project plan view and figure 3, typical beach profile in EA). The proposed borrow area is located within the ebb shoal northeast of Bakers Haulover Inlet in 10 to 20 feet of water (figures 1 & 4 in EA).

c. Authority and Purpose. Initial authorization came from the Flood Control Act of 1968 authorization of the Beach Erosion Control and Hurricane Protection (BEC & HP) Project for Dade County, Florida. In addition, Section 69 of the 1974 Water Resources Act (P.L. 93-251 dated 7 March 1974) included the initial construction by non-Federal interests of the 0.85 mile segment along Bal Harbour Village, immediately south of Bakers Haulover Inlet. The authorized project, as described in HD 335/90/2, provided for the construction of a protective/recreational beach and a protective dune for 9.3 miles of shoreline between Government Cut and Baker's Haulover Inlet (encompassing Miami Beach, Surfside and Bal Harbour) and for the construction of a protective/recreational beach along the 1.2 miles of shoreline at Haulover Beach Park. The Supplemental Appropriations Act of 1985 and the Water Resources Development Act of 1986 (Public Law 99-662) provided authority for extending the northern limit of the authorized project to include the construction of a protective beach along the 2.5 mile reach of shoreline north of Haulover Beach Park (Sunny Isles) and for periodic nourishment of the new beach. This authority also provided for the extension of the period of Federal participation in the cost of nourishing the authorized 1968 BEC & HP Project for Dade County, which covered 10.5 miles of shoreline extending from Government Cut north to the northern boundary of Haulover Beach Park, from 10 years to the 50-year life of the project.

Nourishment of Dade County Beaches has become a necessity to provide storm protection. The purpose of the project is to prevent or reduce loss of public beach front to continuing erosional forces and to prevent or reduce periodic damages and potential risk to life, health, and property in the developed lands adjacent to the beach.

d. General Description of Dredged or Fill Material.

(1) General Characteristics of Material. The material to be excavated is generally light gray to tan, poorly graded shelly sand with a trace of silt and gravel sized shell fragments. The composite mean grain size of the borrow area is 0.54 mm. The silt content ranges from 0.2 to 13.3 percent with an average of 2.7 percent. Large carbonate rock fragments do not occur in the borrow area; therefore, rock removal will not be required.

(2) Quantity of Material. The amount material needed for the 2,600-foot length of beach to be renourished is estimated at 114,000 cubic yards.

(3) Source of Material. The proposed borrow area for this renourishment is the ebb shoal at Bakers Haulover Inlet. The area is located approximately 2,000 feet offshore, and just northeast of the inlet in 10 to 20 feet of water (figures 1 & 4 in EA).

e. Description of the Proposed Construction Site.

(1) Location. The location of the beach fill is the northern 2,600 feet of Haulover Beach Park, Dade County, Florida. Refer to figure 2 in EA.

(2) Size. The proposed fill is approximately 2,600 feet long with a berm width of 120 feet.

(3) Type of Site. The site for disposal of the sand material is a segment of eroded, sandy, recreational beach and inshore seabed.

(4) Type of Habitat. The beach disposal area consists of a currently eroding carbonate and quartz sand beach and inshore seabed. The borrow area is characterized by a sandy bottom. There are no known seagrass beds or hardgrounds in the borrow area.

(5) Timing and Duration of Dredging. The exact timing of nourishment is not known. It is anticipated that construction will occur during the fall/winter of 2002.

f. Description of Disposal Method. It is anticipated that the material will be obtained from the ebb shoal borrow area using a hydraulic pipeline dredge. Once the material is pumped on the beach, grading will be performed using construction equipment to achieve the desired construction profile.

II. Factual Determinations

a. Physical Substrate Determinations.

(1) Substrate Elevation and Slope. The beach fill will be constructed with a berm elevation of +9.0 feet MWL and a width of 120 feet from the ECL. The front slope of the beach fill will be 1 vertical on 10 horizontal. Refer to figure 3 in the EA.

(2) Type of Fill Material. Sand from the borrow area has a high carbonate (shell) content and ranges in size from fine to coarse.

(3) Dredge/Fill Material Movement. The fill material will be subject to erosion by waves with the net movement of fill material to the south.

(4) Physical Effects on Benthos. Some benthic organisms that are not mobile may be lost during dredging and may be covered by the beach fill. Recolonization soon after project completion is expected to replace those organisms that do not survive project construction. It is anticipated that no long-term adverse impacts will occur.

b. Water Circulation, Fluctuation and Salinity Determination.

(1) Water Column Effects. During dredging and beach fill operations, turbidity will increase temporarily in the water column. The increased turbidity will be short-term; therefore fill placement will have no long-term or significant impacts, if any, on salinity, water chemistry, clarity, color, odor, taste, dissolved gas levels, nutrients or eutrophication.

(2) Current Patterns and Circulation. Net movement of water is from the north to the south. The project will have no significant effect on existing current patterns, current flow, velocity, stratification, or the hydrologic regime in the area.

(3) Normal Water Level Fluctuations and Salinity Gradients. Mean tidal range in the project area is 3.5 feet with a spring tide range of approximately 4.1 feet. Salinity is that of oceanic water. Fill placement will not affect normal tide fluctuations or salinity.

c. Suspended Particulate/Turbidity Determinations.

(1) Expected Changes in Suspended Particulates and Turbidity Levels in the Vicinity of the Disposal Site. There may be a temporary increase in turbidity levels in the project area during dredging and along the beach fill sites during discharge. Turbidity will be short-term and localized and no significant adverse impacts are expected. State water quality standards for turbidity outside an allowable mixing zone will not be exceeded.

(2) Effects on the Chemical and Physical Properties of the Water Column. The sea floor at this location is characterized by a large sandy shoal. There would be little, if any adverse effects to chemical and physical properties of the water as a result of the use of the proposed borrow area.

(a) Light Penetration. Some decrease in light penetration may occur in the immediate vicinity of the dredging and beach fill areas. This effect will be temporary, limited to the immediate area of construction, and will have no adverse impact on the environment.

(b) Dissolved Oxygen. Dissolved oxygen levels will not be altered by this project due to the high energy wave environment and associated adequate reaeration rates.

(c) Toxic Metals, Organics, and Pathogens. No toxic metals, organics, or pathogens are expected to be released by the project.

(d) Aesthetics. The aesthetic quality of the water in the immediate area of the project will be reduced during construction due to increased turbidity. This will be a short-term and localized condition. The placement of clean beach compatible sand on an erosive beach will likely improve the aesthetic quality of the immediate area.

(3) Effects on Biota.

(a) Primary Productivity and Photosynthesis. Primary productivity is not a recognized, significant phenomenon in the surf zone, where a temporarily increased level of suspended particulates will occur. There will be no effect on the nearshore productivity as a result of the proposed beach fill.

(b) Suspension/Filter Feeders. An increase in turbidity could adversely impact burrowing invertebrate filter feeders within and adjacent to the immediate construction area. It is not expected that a short-term, temporary increase in turbidity will have any long-term negative impact on these highly fecund organisms.

(c) Sight Feeders. No significant impacts on these organisms are expected as the majority of sight feeders are highly motile and can move outside the project area.

d. Contaminant Determinations. Material which will be dredged from the proposed borrow site will not introduce, relocate, or increase contaminants at the fill area. The material is clean sand compatible with the existing beach.

e. Aquatic Ecosystem and Organism Determinations. The fill material that will be dredged from the proposed borrow area and used in the beach erosion control project is similar enough to the

existing substrate so that no impacts are expected. The materials meet the exclusion criteria, therefore, no additional chemical-biological interactive testing will be required.

(1) Effects on Plankton. No adverse impacts on autotrophic or heterotrophic organisms are anticipated.

(2) Effects on Benthos. Some benthic organisms will be buried by the beach fill. Benthic organisms found in the intertidal areas along the project beach are adapted for existence in an area with considerable substrate movement, thus most will be able to burrow up through the fill material. Recolonization is expected to occur within a year after construction activities cease. No adverse long-term impacts to non-motile or motile benthic invertebrates are anticipated. Similar impacts to benthic organisms within the area to be dredged are expected.

(3) Effects on Nekton. No adverse impacts to nektonic species are anticipated.

(4) Effects on the Aquatic Food Web. No adverse long-term impact to any trophic group in the food web is anticipated.

(5) Effects on Special Aquatic Sites.

(a) Hardground and Coral Reef Communities. There are no hardground or coral reef communities located in the immediate nearshore area that would be impacted by beach fill activities.

(6) Endangered and Threatened Species. There will be no significant adverse impacts on any threatened or endangered species or on critical habitat of any threatened or endangered species. Refer to Section 5.0 in the EA for measures that will be implemented to protect endangered and threatened species.

(7) Other Wildlife. No adverse impacts to small foraging mammals, reptiles, or wading birds, or wildlife in general are expected.

(8) Actions to Minimize Impacts. All practical safeguards will be taken during construction to preserve and enhance environmental, aesthetic, recreational, and economic values in the project area. Specific precautions are discussed elsewhere in this 404(b) evaluation and in the EA for this project (refer to Sections 4.0 and 5.0 in the EA).

f. Proposed Disposal Site Determinations.

(1) Mixing Zone Determination. Clean sand, compatible with the existing beach, would be placed on the beach. This will not cause unacceptable changes in the mixing zone water quality requirements as specified by the State of Florida's Water Quality Certification permit procedures. No adverse impacts related to depth, current velocity, direction and variability, degree of turbulence, stratification, or ambient concentrations of constituents are expected from implementation of the project.

(2) Determination of Compliance with Applicable Water Quality Standards. Because of the inert nature of the material to be dredged, Class III water quality standards will not be violated.

(3) Potential Effects on Human Use Characteristics.

(a) Municipal and Private Water Supplies. No municipal or private water supplies will be impacted by the implementation of the project.

(b) Recreational and Commercial Fisheries. Fishing in the immediate construction area will be prohibited during construction. Otherwise, recreational and commercial fisheries will not be impacted by the implementation of the project.

(c) Water Related Recreation. Beach/water related recreation in the immediate vicinity of construction will be prohibited during construction activities. This will be a short-term impact.